Radiator Removal During OBS EMI Testing

M. Campell E. Ortiz M. Swift Updated 6/05/07

- Build frame from 80/20 frame material
- Frame rolls up to Radiator
- Mounts to Adapter Plates that are mounted to the Radiator Handling inserts
- Disconnect Radiator from LAT
- Roll Radiator away from OBS
- Radiator is stored in Frame until ready for installation
- Installation is reverse of removal

Radiator in Frame



Radiator Attachment & Alignment

•Slotted frame allows for vertical alignment

•Slotted adapter plate allows for horizontal alignment

•Threaded stem casters at each corner allow frame assembly to be rotated to square to the panel face

•Bolt to existing Radiator handling inserts



Status

- Design Complete, drawing is 75%
- Stress Analysis in work, ECD 6/7
- Framing is in transit, due 6/6 (recv'd) and 6/7
 - Cost ~\$1000
- Adapter in work in SLAC shop, ECD 6/7/07
 - estimated cost \$200 each X 4
- Proof load procedure in work
- Radiator removal procedure draft out for review

- Frame Assembly will be built up at SLAC per LAT-DS-08881
 - Frame assembly will be squared up on large surface table prior to final torque of fasteners
- Frame Assembly will be proof loaded at SLAC per LAT-DS-08881
 - 2X mass Radiator simulator bolted into frame
- Ship assembled to GD via truck
- GD and NASA review design and procedure

- 80/20 Framing material is high strength aluminum alloy
 - Modular design off the shelf components
 - Bolted connections (5/16" dia. fasteners)
- Frame interfaces with Radiator Handling inserts (1/4-28 fasteners)
- Frame design minimizes shear and bending loads going into Radiator

Design (cont)

• 1515 Extrusion

Part No.	1515
Material	6105-T5
Finish	Clear Anodized
Weight Per Foot	1.3433 Lbs.
	97" - Part No. 1515-97
Stock Length (+/125")	145" - Part No. 1515-145
	242" - Part No. 1515-242
Marrant Of Inantia	IX=.2524"4
woment of inertia	IY=.2524"4
Estimated Area	1.1540 Sq. In.



Design (cont)

Fractional Profile Standards

- Yield strength 35,000 lbs. /sq. in. minimum
- Tensile strength 38,000 lbs. /sq. in. minimum
- Elongation A5 minimum 10%
- Elongation A10 minimum 8%
- Elasticity E approximately 10,200 k lbs./sq.in.
- Rockwell hardness approximately E-88
- Extrusion conforming to DIN 17 615 specifications
- Twist per foot of length not to exceed .25 degree and total twist over 20 feet of length not to exceed 1.5 degrees
- Flatness .004" per inch of width
- Straightness 0.0125" per foot of length, not to exceed .120" over 20 feet of length
- Unless otherwise specified, all extrusions will have etch and clear (204R1) anodizing with depth of .0004" and surface hardness of approximately 250 HV (anodized profiles should not be welded because of toxic fumes)

- Structural analysis of the frame ECD 6/7
 - Details of analysis are found in separate package (LAT-TD-XXXXX)
 - Static and dynamic handling loads considered
 - Appropriate MGSE Factors of Safety are applied
- Tip over analysis complete
 - counterweight applied at rear leg to prevent tipping under lateral handling loads
 - high margins of safety against tipping
- Stress analysis includes
 - simple FEA model of radiator in frame created
 - interface loads at radiator inserts calculated
 - frame joint loads calculated
 - member stresses calculated
 - margins of safety are all high

Schedule

	A	Task Name	Duration	Start	Finish	Predecessors	Б	07		N	∕laγ∶	20, '0)7			May 2	7,'0	7		Jun	3, '0	7		J	lun 11	D, 'O7			Jun	a 17, 'I
	Č		2 41 411011					WI	F	S S	S M	IT N	W 1	r F	S S	S M	ΤV	۷T	F S	SI	VI T	WT	F	s s	S M	τw	TF	S	SI	ΜŤ
1	\checkmark	Design	4 days	Wed 5/23/07	Tue 5/29/07		Τ					0																		
2		Analysis	8 days	Tue 5/29/07	Thu 6/7/07	1FS-7 days										Ģ														
3		Order / Recv framing	5 days 🕂	Thu 5/31/07	Wed 6/6/07	1															•	ŋ								
4		Order / Recv adapter plate	5 days	Fri 6/1/07	Thu 6/7/07	1																								
5		Assemble frame	2 days	Thu 6/7/07	Fri 6/8/07	3																	-							
6		Proof load	1 day	Mon 6/11/07	Mon 6/11/07	5,4																				h				
7		ship to GD	2 days	Tue 6/12/07	Wed 6/13/07	6																					ŋ			
8		Inspect / Clean	1 day	Thu 6/14/07	Thu 6/14/07	7	Τ																				Ľ.			
9		Procedure released	8 days	Mon 6/4/07	Wed 6/13/07	1																					┣┐│			
10		RFU	0 days	Thu 6/14/07	Thu 6/14/07	9,8	Τ																				¥	6/14	l	

Timing

- -Y Radiator would be removed between EMI test segments when OBS needs to be rotated
- OBS is moved to center of chamber and large door is opened
- OBS is on test stand casters
- Test cabling is disconnected for the move

Approx Frame Footprint 80 x 48"



